

Lean Construction Institute

Building Knowledge in Design and Construction

Please comply with the Lean Construction Institute's Usage Policies and Attribution Guidelines at <http://www.leanconstruction.org/usage.pdf> when using this file. Thank you.

Lean Thinking: An Introduction for LCI-Wisconsin's Community of Practice



BOLDT




Will Lichtig
LCI Wisconsin
Milwaukee, Wisc.
March 1, 2011

Purpose

- Common Vocabulary
- **Fundamental Principles**
- **Basic Practices**



Flipping the Tarp . . .



Change the observer

Ohno's World



© 2011 All Rights Reserved

So, what is Lean?




© 2011 All Rights Reserved

On Complexity & Simplicity

I would not give a fig for the simplicity this side of complexity, but I would give my life for the simplicity on the other side of complexity.

Oliver Wendell Holmes, Jr.




© 2011 All Rights Reserved

Basic Lean Principles


Complex systems must be managed to see problems, solve problems, and share what is learned, all while insisting that leaders cultivate these capabilities throughout the organization.

– Steven Spear



© 2011 All Rights Reserved

Ohno Circle



© 2011 All Rights Reserved


Engineer Ohno's 7 Types of Waste

1. Defects or errors
2. Overproduction of goods not needed
3. Inventories of goods awaiting processing or consumption
4. Over processing
5. Motion – people, equipment, tools
6. Transport of goods
7. Waiting

© 2011 All Rights Reserved



© 2010 Lean Construction Institute used with permission of IPD™



© 2010 Lean Construction Institute used with permission of IPD™



1,500 Ton Centrifugal Chiller

© 2010 Lean Construction Institute used with permission of IPD™

Planning Considerations

- Delay decisions to the last responsible moment
- Create pull schedules
- Only do work that releases downstream crews (important also in design)
- Focus on reliability of work flow


© 2010 Lean Construction Institute used with permission of IPD™





Your Predictions

- Duration – Design and Construction ?
- Cost – Design and Construction ?

© 2010 Lean Construction Institute used with permission of IPD™



© 2010 Lean Construction Institute used with permission of IPD™












Contract Date	12/30/03
Permit Issued	4/14/04
Work Begins on Site	4/16/04
Plant Ready to Go	7/28/04
GMP	\$6,000,000
Final cost with normal markup	\$5,400,000
IPD savings against GMP	\$600,000



© 2010 Lean Construction Institute used with permission of IPD™





Understanding Lean Project Delivery




© 2010 Lean Construction Institute used with permission of IPD™






“Buildings Leak at the Intersection of Contracts”




Todd Zabelle





Courtesy of SSM Cardinal Glennon







Five Big Ideas





Courtesy LCI









Dependence & Variation



The Parade of Trades™



Lean Comes to Construction – Towards Root Cause



Research Findings -- Problem

Average -- 54 %

© 2011 All Rights Reserved

Fundamental Principles

1. Dependence and variation affect system performance
2. Batch size affects system performance
3. Workflow reliability directly affects system speed and cost.
4. All plans are forecasts, all forecasts are wrong, further in advance – more wrong, more detail – more wrong.

Even bureaucratic command-and-control won't do; it is too difficult to know who should do what and who actually is doing what with enough clarity and timeliness to direct them appropriately in a top-down fashion.

– Steven Spear




Last Planner™ System

1. Produce predictable workflow
2. Produce rapid learning
3. Focused on making work ready and using commitment based planning


Last Planner® System

5 - Connected Conversations

SHOULD	Master Scheduling Milestones	Set milestones
	Phase "Pull" Planning	Specify handoffs
CAN	Make Work Ready Planning	Make ready & Launch replanning when needed
WILL	Weekly Work Planning	Promise
DID	Learning	Measure PPC & Act on reasons for failure to keep promises








Fundamental Principles

1. “Makers” are customers who should participate in design.
2. Cost and constructability should be design criteria, rather than an outputs.
3. Project-wide optimization requires cross-functional participation.
4. The process of construction needs to be designed, as well as the product.


Design as Knowledge Development

The capacity to be faster and stronger in the design, operation and improvement of complex systems depends on seeing where knowledge is needed, generating new knowledge, and sharing and intermingling that new knowledge . . .


– Steven Spear



Pull Planning & Value Stream Mapping






PDCA Thinking in Design





Change by Design

IPD Target Value Design Clusters









Fundamental Principles

- The commercial system must be aligned with the other domains
- Lean calls for management by process, not by results
- Encourage Prudent Risk Taking
- Eliminate Hidden Contingency (Howell's new waste)









Open-Face Risk Management





Profit Pool / Combined Contingency







	Organization	Operating System	Commercial
Old	Hierarchical Siloed Command & Control	CPM Specialists Parts	Lump Sum Low Price
IPD	Collaborative Flat Consensus	Lean Sustainable BIM	Entrepreneurial Collective Best Value



The daily chatter of imperfect systems is not unavoidable noise to be griped about or ignored.

High velocity organizations . . . do not encourage or admire workarounds, firefighting, or heroic measures. They want to understand and solve problems, not put up with them.



The Path to New Leadership

© 2011 All Rights Reserved




Will Lichtig

Vice President, Business and
Process Development

The Boldt Company

will.lichtig@boldt.com

916.583.5617



The Last Planner – Introduction and Examples

Jeff Niesen

Jeff.Niesen@Boldt.com

608-250-8414

BOLDT[®]

The Last Planner

- What is the Last Planner and why it is an important element of Lean Construction
- How the Last Planner works
- Examples of Last Planner Implementation

What is the “Last Planner”


- Weekly production planning meeting
- Not a traditional “progress meeting”
- Not traditional “scheduling”
- Who are the Last Planners?
 - The people doing the work
- Collaborative & participative meeting
- Learning environment

Why the Last Planner is a critical element in Lean Construction

- Objectives of the meeting
 - Create Flow
 - Identify constraints
 - Properly sequence work
 - Use Pull to do the right work at the right time
 - Eliminate Waste
 - Secure commitments (Reliable Promises)
 - Create individual accountability
 - Measure success (PPC)
 - Learn (continuous improvement)

Hierarchy of Planning System

Drilling Down From Strategic Scheduling Into Production Planning and Detailed Work Assignments (Magnification)



Reliability Matters

- Traditional project meetings – commitment free zone?
- Construction industry – systemic lying?
- Typical superintendent – overly optimistic?


Traditional Management

Plan Reliability Data

Contractor 1	33 %
Contractor 2	52 %
Contractor 3	61 %
Contractor 4	70 %
Contractor 5	64 %
Contractor 6	57 %
Contractor 7	45 %
<hr/>	
Average	54 %


How many of the tasks you thought would be complete during the week actually got done?

Forming the Weekly Work Plan




Unless commitment is made, there are only promises and hopes... but no plans. - Peter Drucker

Certainty of Failure



Highest Probability of Task Completion



Reliable Promises

Five Basic Elements of a Promise
Speaker (performer) – This is you. Be clear that you are making the commitment, not someone else.
Listener (customer) – This is the customer or someone depending on your performance. He or she already made a request.
Mutually understood Conditions of Satisfaction – Many breakdowns occur due to a misunderstanding of what is being requested. What is obvious to one is not obvious to the other, particularly when people may have just met each other.
Future action – When we make a promise we are saying that sometime in the future (before the due date) we will perform some action to bring about the desired outcome or conditions of satisfaction.
Due date – This is the second source of miscoordination. One person is thinking “now” while the other person is thinking “when I get around to it”. Always err on the side of explicitly specifying the required date.

Five Elements of a Reliable Promise
I am competent (able) to perform the task and have the wherewithal or I have access to both with the help of others.
I understand or have estimated how much time it will take me to perform this task.
I have (already) blocked out time in my calendar that I need (estimated) to perform the task.
I am freely and sincerely making this promise . I am not having a private unspoken conversation to the contrary.
I know that when I make a promise I may not be able to fulfill it. I will be responsible for any upset that occurs should I not be able to perform the task , including any negative consequences that may come my way.

How the Last Planner Works

- Three major elements in the Last Planner
 - Look ahead (typically 6 weeks)
 - Shape work flow
 - Identify constraints
 - Weekly work plan
 - Secure specific commitments for the coming week
 - Review PPC
 - Work that is not completed goes back in the lookahead schedule
 - This step includes learning by asking why

Sample Six Week Lookahead

BOLDT										Six Week Lookahead										Constraints Analysis									
SORT	Repeat	Project: Sample Industrial Project		Boldt Schedule Contact: e-mail: Phone: Fax:							Safety	Contracts / C.O.'s	Submittals/Eng	RFI's	Materials	Labor	Equipment	Prerequisite Work	Space	Week of _____									
		Activity	Responsible Party	5/14	5/21	5/28	6/4	6/11	6/18	Explanation of Constraints										Action Required By:									
1	X	Roof repair @ existing building	Boldt	X																									
1		Install dye tanks	XL Mech	X									X	X	X			Verify installer	Brian T										
1		Ext fgs, walls, & col North H-L, 5-11	Boldt	X																									
1		Underslab rough in	XL Mech/K&W	X								X	X																
1	X	Form & pour coater pits	Boldt	X									X	X				Excavation to be complete 5/11	John H										
1		Prep existing parapet wall (East)	Boldt	X																									
1		Erect col lines 5 & 6 - O to C	Boldt	X									X	X				Structural steel delivery	Matt H										
1		Steam shower PLC panel modifications	K & W	X	X							X	X	X															
1		FRP machine track col lines 6 to 8 - I to M	Boldt	X	X								X	X				Rebar delivery	Matt H										
1		Demo 6" carbon line	XL Mech	X	X																								
1		Dye tank discharge pump installation	XL Mech	X	X																								
1		Thaw with ground heaters	Boldt	X	X	X	X	X																					
2		Install water units for #11 coaters in basement	XL Mech	X								X	X	X	X			Shipped from Harrisburg / 2nd Unit needed											
2		Figs, walls, & col A-C, 1-6	Boldt	X																									
2		Install Roof Col Lines 5-6 O-C	Boldt	X									X	X				Structural steel delivery 5/11 AM	Matt H										
2		FRP machine track col lines 6 to 8 - M to P	Boldt	X																									
2		Erect steel col lines 6 to 9 - I to A	Boldt	X																									
2		Install roof col lines 5 & 6 - O to C	Boldt	X									X	X				Structural steel delivery	Matt H										
2		FRP machine track col lines 6 to 8 - I to F	Boldt	X									X	X				Anchor bolt delivery	Matt H										
2		Install siding col lines 6 - O to A	Boldt	X									X	X				Verify siding color & delivery	John H										
2		FRP machine track col lines 6 to 8 - F to C	Boldt	X																									
2		Complete reel foundations	Boldt	X	X							X	X																
2		FRP SOG col lines 5 & 6 - N to H	Boldt	X	X																								
2		Cure concrete col lines 6 to 8 - I to M	Boldt	X	X																								
2		Bench board PLC modifications	K & W	X	X	X						X	X	X				Need misc components to start	Mike L										
2		Cure concrete col lines 6 to 8 - M to P	Boldt	X	X	X																							
3		Erect steel col lines 6 to 9 - I to O	Boldt	X									X	X				Structural steel delivery	Matt H										
3		Install siding col lines 6 to 9 - A to O	Boldt	X	X								X	X				Siding delivery	John H										
3		Cure concrete col lines 6 to 8 - I to F	Boldt	X	X																								
3		FRP SOG col lines 5 & 6 - H to C	Boldt	X	X																								
4		Install sprinkler system	Boldt	X								X	X	X				Procurement - Need to expedite material	Jim B										
4		Erect steel col lines 5 to 9 - O to Q	Boldt	X									X	X				Structural steel delivery	Matt H										
4		Erect block house	Boldt	X	X							X	X	X															
4		Install roof col lines 6 to 9 - A to O	Boldt	X	X								X	X				Structural steel delivery	Matt H										
4		Blockhouse masonry & roof	Boldt	X	X							X	X	X				RFC Blockhouse dwgs	Lee A										
4		Install make up air ductwork	Bassett	X	X	X						X	X	X				Lead time for fab & delivery	Mike S										
4		Install hi-bay lights	K & W	X	X	X						X	X	X				Specialty light delivery	Scott R										
5		Install make up air unit	Bassett	X																									

Sample Six Week Lookahead (page 2)

SORT	Repeat	Project: Sample Industrial Project		Boldt Schedule Contact: e-mail: Phone: Fax:																	Week of _____	
		X = Repeated Items									Safety	Contracts / C.O.'s Submittals/Eng	RFI's	Materials	Labor	Equipment	Prerequisite Work	Space	Explanation of Constraints	Action Required By:		
		Activity	Responsible Party	5/14	5/21	5/28	6/4	6/11	6/18													
5		Ready temporary heat col lines 5 to 9 - A to Q	Boldt					X											Availability of heaters	Matt H		
5		Install siding & roof col lines 5 to 9 - O to Q	Boldt					X						X	X				Delivery of siding & structural steel	Matt H		
5		Erect steel col lines 9 to 11 - F to Q	Boldt					X						X	X				Structural steel delivery	Matt H		
5		Install roof curbs col lines 6 to 9 - A to Q	Boldt					X														
5		Install exhaust fans & skylights on roof curbs	Boldt					X						X	X				Exhaust fans & skylight delivery (Tinted glass)	John H		
5		Energize temporary heat	Boldt					X						X	X							
5		Machine erection	Boldt					X	X					X	X				Verify delivery of equipment	John H		
6		FRP SOG col lines 5 & 6 - N to Q	Boldt						X													
6		Install siding col lines 9 to 11 - F to Q	Boldt						X					X	X				Siding delivery	John H		
6		Erect steel col lines 1 to 5 - A to C	Boldt						X					X	X				Structural steel delivery	Matt H		
6		Install masonry parapet wall col lines 1 to 5 - C	Boldt						X					X	X				Availability of "Mason" manpower	John H		
6		FRP SOG col lines 6 to 8 - P to Q	Boldt						X													
6		Erect coater program room	Boldt						X		X	X	X						Mill to approve dwgs	Steve B		
6		Install building E & I	K & W						X		X	X	X						RFC Electrical dwgs 5/21	Lee A		
6		Install gas piping AMU & unit heaters	XL Mech						X		X	X	X						Procurement of AMU & unit heaters	Jim B		
6		Install drives/transformers/bus duct	K & W						X		X	X	X						Need miscellaneous components	Mike L		
6		Install mill air	XL Mech						X		X	X	X						RFC Piping dwgs 5/15	Lee A		
6		Install mill water	XL Mech						X		X	X	X						RFC Piping dwgs 5/15	Lee A		
6		Install mill steam	XL Mech						X		X	X	X						RFC Piping dwgs 5/15	Lee A		
6		Install gas piping to machine	XL Mech						X		X	X	X						RFC Piping dwgs 5/15	Lee A		
6		Install instr & valves	XL Mech						X		X	X	X						Need submittals for valve procurement	Lee A		

Sample Six Week Lookahead (blow-up)

BOLDT																				
Six Week Lookahead										Constraints Analysis										
SORT	Repeat	Project: Sample Industrial Project		Boldt Schedule Contact: e-mail: Phone: Fax:						Safety	Contracts / C.O.'s	Submittals/Eng	RFI's	Materials	Labor	Equipment	Prerequisite Work	Space	Week of _____	
		Activity	Responsible Party	5/14	5/21	5/28	6/4	6/11	6/18										Explanation of Constraints	Action Required By:
1	X	Roof repair @ existing building	Boldt	X																
1		Install dye tanks	XL Mech	X									x	x	x			Verify installer	Brian T	
1		Ext ftgs, walls, & col North H-L, 5-11	Boldt	X																
1		Underslab rough in	XL Mech/K&W	X							x	x								
1	X	Form & pour coater pits	Boldt	X									x	x				Excavation to be complete 5/11	John H	
1		Prep existing parapet wall (East)	Boldt	X																
1		Erect col lines 5 & 6 - O to C	Boldt	X									x	x				Structural steel delivery	Matt H	
1		Steam shower PLC panel modifications	K & W	X	X						x	x	x							
1		FRP machine track col lines 6 to 8 - I to M	Boldt	X	X								x	x				Rebar delivery	Matt H	
1		Demo 6" carbon line	XL Mech	X	X															
1		Dye tank discharge pump installation	XL Mech	X	X															
1		Thaw with ground heaters	Boldt	X	X	X	X	X												
2		Install water units for #11 coaters in basement	XL Mech		X						x	x	x	x				Shipped from Harrisburg / 2nd Unit needed		
2		Ftgs, walls, & col A-C, 1-6	Boldt		X															
2		Install Roof Col Lines 5-6 O-C	Boldt		X								x	x				Structural steel delivery 5/11 AM	Matt H	
2		FRP machine track col lines 6 to 8 - M to P	Boldt		X															
2		Erect steel col lines 6 to 9 - I to A	Boldt		X															
2		Install roof col lines 5 & 6 - O to C	Boldt		X								x	x				Structural steel delivery	Matt H	
2		FRP machine track col lines 6 to 8 - I to F	Boldt		X								x	x				Anchor bolt delivery	Matt H	
2		Install siding col lines 6 - O to A	Boldt		X								x	x				Verify siding color & delivery	John H	

Sample Weekly Work Plan


BOLDT				Boldt Schedule Contact: e-mail: Phone: Fax:								
Project: Sample Industrial Project												
Weekly Work Plan				X = Repeated Items		Week of						
Assignment Description				Make Ready Needs								
Sort	Repeat	Remember the Five Criteria for Release of Assignments Specific, Sound, Sequenced, Sized, Safe	Responsible Party	Work that Must and Can Be Performed Prior to Release of this Assignment		M	T	W	T	F	S	Comments
1		Prep existing parapet wall (East)	Mitch N			X	X					
2		Roof repair @ existing building	Mitch N			X	X	X				
5		Ext ftgs. walls, & col North H-L, 5-11	Mitch N			X	X	X	X	X		
5	X	Form & pour coater pits	Mitch N			X	X	X	X	X		
5	X	Install dye tanks	Bob H			X	X	X	X	X		
5		Start FRP machine track col lines 6 to 8	Mitch N					X	X	X		
5		Steam shower PLC modifications from hood to nozzles	John W			X	X	X	X	X		
5		Underslab rough in - All	Bob H/JohnW			X	X	X	X	X		
5		Erect col lines 5 & 6 - O to C	Mitch N			X	X	X	X	X		
6		50% Dye tank discharge pump installation	Bob H			X	X	X	X	X	X	
6		Demo 6" carbon line from existing dye tank to #18	Bob H			X	X	X	X	X	X	

Sample Percent Planed Complete (PPC)

BOLDT		Project: Sample Industrial Project		Boldt Schedule Contact: e-mail: Phone: Fax:		Week of	
Planned Percent Complete				X = Repeated Items		PPC = 83%	
Assignment Description				Make Ready Needs		PPC Analysis	
REPEAT	Remember the Five Criteria for Release of Assignments Specific, Sound, Sequenced, Sized, Safe	Responsible Party	Work that Must and Can Be Performed Prior to Release of this Assignment	Y	N	Reasons For Variance	
	Install grounding grid	John W		y			
x	Backfill ext fgs South 9-5, A	Mitch N		y			
	E, F, P remaining int column fgs	Mitch N		y			
	Backfill ext fgs South 11-9, A-F	Mitch N		y			
	Ext fgs, walls, & col North M-Q, 5-11	Mitch N		y			
	Form & pour coater pits	Mitch N			n		Design Change
	Install dye tanks	Bob H			n		Delivery Monday
	Install roof drain piping	Bob H		y			
	3" Mill airline	Bob H		y			
	Run dye system tubing	Bob H		y			
	3" coating line from tank farms to #18 Bldg	Bob H		y			
	Install 1" Dye line returns	Bob H		y			


Sample PPC Tracking

Planned Percent Complete
Sample Industrial Project



Sample Plan Failure Analysis

Variance Tracking Chart
Sample Industrial Project



Pull Scheduling Meeting




Last Planner Meetings



Wisconsin Institutes for Medical Research (WIMR)



WIMR Center Tower Schedule Development Plan



Weekly Last Planner Meetings



LAST PLANNER

General Outline

Who attends? A Superintendent and/or a PM from each Subcontractor
When? 9:00 am Thursday
Where? WIMR Conference Room
How long? 1 Hour

Procedure

1. Complete the Attendance Log.
2. Review the Top Three Safety Items of the Week.
3. Complete typical Daily Huddle
 - a. Review Wednesday's tasks for completion.
 - b. Review Thursday's scheduled work.
4. Review PPC.
5. Discuss Constraints Log.
6. Confirm tasks previously scheduled for Week 1 (formerly Week 2) are still accurate. Develop daily tasks for Week 2.
7. Review Pull Schedule for milestone accuracy.

Rules

- **Prior to reschedule, every incomplete task receives a:**
 - **Late sticker (with original date)**
 - **Reason for incompleteness (constraint no.)**
- **If rescheduled tasks affect a Milestone Date, the team must adjust the Pull Schedule to maintain original dates or a separate meeting must be scheduled.**
- **Side conversations that focus on problem solving instead of project planning must be tabled and added to the Sidebar Log for later discussion.**

Goals

- **Make Reliable Commitments!**
- **Work to Eliminate Constraints!**

Weekly Last Planner Meetings



LAST PLANNER

General Outline

- Who attends?** A Superintendent and/or a PM from each Subcontractor
When? 9:00 am Thursday
Where? WIMR Conference Room
How long? 1 Hour

Procedure

1. Complete the Attendance Log.
2. Review the Top Three Safety Items of the Week.
3. Complete typical Daily Huddle
 - a. Review Wednesday's tasks for completion.
 - b. Review Thursday's scheduled work.
4. Review PPC.
5. Discuss Constraints Log.
6. Confirm tasks previously scheduled for Week 1 (formerly Week 2) are still accurate. Develop daily tasks for Week 2.
7. Review Pull Schedule for milestone accuracy.

Weekly Last Planner Meetings

Rules

- **Prior to reschedule, every incomplete task receives a:**
 - **Late sticker (with original date)**
 - **Reason for incompleteness (constraint no.)**
- **If rescheduled tasks affect a Milestone Date, the team must adjust the Pull Schedule to maintain original dates or a separate meeting must be scheduled.**
- **Side conversations that focus on problem solving instead of project planning must be tabled and added to the Sidebar Log for later discussion.**

Goals

- **Make Reliable Commitments!**
- **Work to Eliminate Constraints!**

Daily Huddle



DAILY HUDDLE

General Outline

Who attends?	A Superintendent or Foreman from each Subcontractor
When?	6:45 am Monday, Tuesday, Wednesday, and Friday
Where?	Boldt jobsite plan area
How long?	No more than 15 minutes per meeting

Procedure

1. Complete the Attendance Log.
2. Review previous day's tasks for completion.
 - If a previous day's task was completed, the Subcontractor attaches a Completion Sticker to the tag and moves it to the Completed Column.
 - If the task was not completed, the Subcontractor provides a reason. If the reason is a constraint that requires resolve from outside the Daily Huddle, it must be entered on the Constraints Log.
3. Review current day's tasks and finalize any coordination required for successful completion.
4. Add/Remove constraints from the Constraints Log.

Rules

- **If a task wasn't completed on time...**
The task must remain where originally scheduled until:
 - The task is completed.
 - Thursday's Last Planner Meeting (for reschedule).
- **If a task is completed early...**
The task receives a completion sticker and moves to the completed column.
- **If a task can be pulled back...**
The task can be rescheduled to an earlier date as long as the Team agrees to the reschedule.

Daily Huddle



DAILY HUDDLE

General Outline

Who attends?	A Superintendent or Forman from each Subcontractor
When?	6:45 am Monday, Tuesday, Wednesday, and Friday
Where?	Boldt jobsite plan area
How long?	No more than 15 minutes per meeting

Procedure


1. Complete the Attendance Log.
2. Review previous day's tasks for completion.
 - If a previous day's task was completed, the Subcontractor attaches a Completion Sticker to the tag and moves it to the Completed Column.
 - If the task was not completed, the Subcontractor provides a reason. If the reason is a constraint that requires resolve from outside the Daily Huddle, it must be entered on the Constraints Log.
3. Review current day's tasks and finalize any coordination required for successful completion.
4. Add/Remove constraints from the Constraints Log.

Daily Huddle

Rules

- **If a task wasn't completed on time...**
The task must remain where originally scheduled until:
 - The task is completed.
 - Thursday's Last Planner Meeting (for reschedule).
- **If a task is completed early...**
The task receives a completion sticker and moves to the completed column.
- **If a task can be pulled back...**
The task can be rescheduled to an earlier date as long as the Team agrees to the reschedule.

WIMR Pull Schedule




Last Planner Example (WIMR) page 1

Six Week Look ahead: Week Ending 2/26/11					Constraints Analysis														
Week Start	WIMR - BP01 Site Prep Work																		
	Activity	Responsible Party	Activity Detail	Week ending 2/26			Weeks Ahead												
				M	T	W	Th	F	S	Sa	Su	30	31	01	02	03	04	05	
Milestones				Click cell to include/exclude Milestone															
Complete BP01 Work																			
General Site Activities																			
	Site Fence Complete	Federal				x	x	x											
1	Install Jersey Barriers	Boldt				x	x	x											
1	Install interior signage	Boldt				x	x	x											
1	Make up small internal signage	Boldt				x	x	x											
1	Install egress man doors	Boldt																	
1	Jersey barriers @	Boldt																	
1	Install fence signage	Boldt																	
1	Loading dock canopy design	Boldt / ZAS																	
1	Install phone at Area of Rescue	Boldt																	
1	Portable toilets on site	Boldt																	
2	Site Logistics Checklist meeting	Boldt																	
2	Install temp site road	Dane County																	
3	Deliver walkable scaffolding at CSC1	Boldt																	
4	Build temp. dock extension	Boldt																	
4	Install egress protection @ CSC	Boldt																	
6	Erect scaffold stair to access L2 from W	Boldt																	
6	Install loading dock canopy	Boldt																	
Tower Crane Installation																			
	Submit tower crane rebar shops	Gerdau				x	x												
	Approve tower crane rebar shops	Hanwood				x	x	x											
	Confirm tower crane elevations	Boldt / ZAS						x											
1	Frost removal at caissons	Dane County																	
1	Prep tower crane locations for caissons	Dane County																	
1	Layout tower cranes	Boldt																	
1	Fab rebar for tower cranes	Gerdau																	
2	Deliver tower crane rebar	Gerdau																	
2	Install caissons	Gillen																	
2	Form tower crane pads	JCP																	
3	Place concrete - tower crane pads	Boldt																	
3	Install grounding for cranes	Pleper																	
3	Install tower crane bases	Reynolds																	
3	Verify generators for cranes	Boldt																	
4	Concrete pad - cure time																		
4	Power for tower cranes	Pleper																	
5	Erect tower cranes	Reynolds																	
East Wedge Area Work																			
	Contract LMI to remove snow	Boldt																	
	Submit Ready-mix designs	Wingra				x													
	Submit rebar shops - area well walls	Gerdau																	
	Mark up plan for Phase 1 and Phase 2	Boldt																	
1	Remove snow	Dane County																	
1	Approve rebar shops - area well walls	Hanwood																	
1	Frost removal - Phase 1	Dane County																	
1	Wedge well layout	Boldt																	
1	Build temp egress stairs for L1 level	Boldt																	
2	Excavate walls - Phase 1	Dane County																	
2	Fab Wall rebar	Gerdau																	
2	Deliver wall rebar - Phase 1	Gerdau																	
2	Form rings / walls - Phase 1	JCP																	
2	Install rebar	Choice																	
2	Place concrete - Phase 1	Boldt																	
2	Strip walls	JCP																	
3	Backfill walls - Phase 1	Dane County																	
3	Wedge - swap egress route	Boldt																	
3	Remove wood stairs from B1 area well	Boldt																	
3	Install sleeves for Storm Sewer	Dane County																	
3	Wedge form walls - Phase 1	JCP																	
4	Deliver rebar - walls Phase 2	Gerdau																	

Last Planner Example (WIMR) page 2

Week Start		Six Week Look ahead: Week Ending 2/26/11																																						
		WIMR - BP01 Site Prep Work		Activity Desc	Week ending 2/26							Weeks Ahead						Constraints Analysis																						
		Activity	Responsible Party		M	T	W	Th	F	S	Su	01	02	03	04	05	06	07	08	09	10	11	12	01	02	03	04	05	06											
4	Remove frost - phase 2	Dane County																																						
4	excavate walls - Phase 2	Dane County																																						
4	Form wedge Walls - Phase 2	JCP																																						
4	Install rebar - walls - Phase 2	Choice																																						
5	Install sleeves for Storm Sewer	Dane County																																						
5	Install conduit for pump electrical	Pieper																																						
5	Place concrete - Phase 2	Boldt																																						
5	Strip walls	JCP																																						
5	Backfill walls - Phase 2	Dane County																																						
5	Install storm sewer	Dane County																																						
5	Install pump	Dane County																																						
6	Raise grade / install storm a East Wedge	Dane County																																						
6	Power to pump	Pieper																																						
6	SOG at area well - B1 level	JCP / Boldt																																						
6	rub walls	Boldt																																						
6	Install new temp. stair @ B1 level area well	Boldt																																						
Center Tower Roof Demo / Prep																																								
	Roofing demo / waterproofing Mtng	Boldt	Finalize plan / schedule																																					
	Remove roof ballast	GBR	L2 and L3 levels																																					
	Remove lightning protection	Pieper																																						
	Temp. Steam relief out wall	GHAC																																						
	Relocate cage wash exhaust	GHAC																																						
	Remove existing roof	GARR	L2 and L3 levels																																					
	Extend existing lightning protection	Pieper																																						
	Install Waterproofing	Zander	L2 and L3 levels																																					

Charter Street Heating Plant (CSHP)



Last Planner Example CSHP page 1

BOLDT arnec Charter Street Heating Plant Rebuild				Six Week Lookahead: Week of 2/21													Constrains Analysis														
Week Start	Activity	Responsible PM	Activity Detail	Week of 2/21							Weeks Ahead						Scheduling	Cost	Eng'g Change	Material Change	Contract Change	Design Change	RFI Change	Labor	Procurement Work	Change Order	C.O.N.				
				M	T	W	T	F	S	S	M	T	W	T	F	S												S			
Technical Leadership Team																															
Review @ Wednesday TLT Meeting				x	x	x	x	x	x	x	x	x	x	x	x	x	x	x													
See Major Equipment Procurement Report																															
1	Sustainable guidelines	Andy	Schedule after reconfiguration of project								x																				
1	Monthly Master Schedule update	Gus	Issue wrap up to state								x																				
2	Submit February Invoice	Gus	Mar. 3																												
2	Fire Protection Sub Approval	Gus	Gus to Jeff for TLT approval - waiting for reconfiguration of project																												
2	Roofing Sub Approval	Jeremy	Jeremy to Jeff for TLT approval																												
3	Pencil review pay application	Jeff N.	review February invoice Mar. 9																												
Events																															
1	DOADSF Furlough Day	N/A	Feb. 21	x																											
General Project																															
2	Fire protection bid package	Gus	Waiting for project reconfiguration																												
2	City Coordination meeting	Gus	1-Mar																												
2	Critical Components of the Work	Maynard	Waiting for project reconfiguration																												
Eastside of Mills St. Dayton Building																															
General																															
1	steam vault	A&O	Design	x	x	x	x	x	x																						
1	Underslab Plumbing	Andy	Amec design with owner approval of steam turbine drives	x	x	x	x	x	x	x															x	x	x				
2	Rebar Submittal	Andy	18 Line L06 to the West																												
1	Equipment Layout	Dan R.	1.06 to the W waiting on reconfiguration	x	x	x	x	x	x	x	x	x	x	x	x																
1	Waterproofing	G & C	Insulation on M line to elevation 91 - Prep work on 16 line M to L4	x	x	x	x	x	x																						
1	Precast	Jeremy	Precast submittals N. & E. Elevation	x	x	x	x	x	x																						
1	Curtain wall	Jeremy	Issue contract and continue shop drawings	x	x	x	x	x	x																						
1	Metal Panels	Jeremy	Issue contract and continue shop drawings	x	x	x	x	x	x																						
1	Roofing	Jeremy	Review Proposals	x	x	x	x	x																							
1	Install Drain tile and backfill foundations	Joe	11.85 to 16 line on M line - 16 line M to L4	x	x	x	x	x	x																						
1	FRPS Southeast Stair Tower 1st thru 5th - Stair #1	Joe	Place wall to 12W	x	x	x	x	x	x	x																					
1	FRPS Interior Footings	Joe	place footings 15 Line to 11.1 - L to L2, to elevation 77'2"	x	x	x	x	x	x																						
1	FRP Transfer structural slab	Joe	Farm and Pour 1st Floor elevated deck at gas vault	x	x																										
1	Install Drain tile and backfill foundations	Joe	Back Fill - 10.8 to 16 line on M line	x	x	x	x	x	x																						
1	Install Drain tile and backfill foundations	Terra	Back Fill - 10.8 to 16 line on M line	x	x	x	x	x	x																						
1	Mass Excavation	Terra	excavate at L6 line	x	x	x	x	x	x																						
1	Earth Retention System	Terra	welding tie backs at F.1 and 11.1 line	x	x	x	x																								
2	Temp heat	Ahern	Pipe through 16 line wall																												
2	Fire Pump Submittal	Gus	Contractor recommendation																												
2	FRPS Building Foundation Walls	Joe	Pour walls - 1.4 to H Line																												
2	New MGE Gas Regulating/Metering Station	MG&E	Install PRV - March 1																												
3	Design Sprinkler Pipe Route	Andy	Waiting for project reconfiguration																												
4	Erect Steel	Andy S.	Start layout Mar. 14 - Install steel Mar 21																												
Phase 3 - ON HOLD/OWNER DECISION																															
###	Install grounding	Joe	11-Feb																												
###	FRPS Building Footings	Joe	11-Feb																												
###	FRPS Building foundation walls	Joe	15-Feb																												
1	Waterproofing	Joe	25-Feb																												
2	Install Drain tile and backfill foundations	Joe	4-Mar																												
Phase 4 - ON HOLD/OWNER DECISION																															
2	Install Grounding	Joe	28-Feb																												
2	FRPS Building Footings	Joe	28-Feb																												
3	Install Drain tile and backfill foundations	Joe	7-Mar																												
Superstructure																															
1	Review & approve 1st tier steel shop drawings	Andy		x	x	x	x	x																							

Last Planner Example CSHP page 2


BOLDT amec [®] Charter Street Heating Plant		Six Week Lookahead: Week of 2/21												Constraints Analysis								
Week Start	Activity	Responsible Party	Activity Detail	Week of 2/21							Weeks Ahead					Bidding	Owner Approval	Design	Procurement	Construction	Commissioning	Closeout
				M	T	W	Th	F	S	S	1	2	3	4	5							
Charter Street Heating Plant																						
Rebuild																						
1	Steel Material Shop Drawings	Skyline	Operating floor I.06 to the East - Under review	x	x	x	x	x	x	x												
5	Fab & Deliver Structural Steel	Joe	Delivery based on current M&I run date 3/21																			
5	Finalize 1st tier steel framing desing	Joe	Steel Erection - Start tier 1 steel - March 21																			
Steam Turbine Generator																						
AMEC Engineering - ON HOLD PENDING STATE APPROVAL - Rescope of work																						
###	New Steam Turbine Generator Loop Diagrams	Eric - Amec	2/28/11 - 4/28/11																			
###	New Steam Turbine Generator Database & Spec Sheet	Eric - Amec	2/28/11 - 9/28/11																			
1	Equipment Layout Design- Dayton ST - Phase 2 STG	Eric - Amec	12/27/10 - 2/16/11							x												
1	P&ID's Internal Review and approval - STG	Eric - Amec	1/14/11 - 1/28/11																			
1	P&ID's - External Review and Approval - STG	Eric - Amec	1/31/11 - 2/14/11							x												
1	New STG Logic & Point List to Novaspect	Eric - Amec	2/15/2011							x												
1	P&ID's Review meeting @ Madison - STG	Eric - Amec	2/15-2/16							x												
1	New STG DCS Configuration by Novaspect	Eric - Amec	2/16-10/25/11							x	x	x										
1	Equipment layout rev & app - Dayton ST - Ph 2 - STG	Eric - Amec	2/17/11-3/2/11							x	x											
1	P&ID's - IFD STG	Eric - Amec	2/25/2011							x												
1	P&ID's to Novaspect - STG	Eric - Amec	2/25/2011							x												
1	P&ID's - IFA - Dayton ST - STG	Eric - Amec	1/28/2011							x												
BOLDT CONSTRUCTION																						
30 N. Mills Street/Verify Contract																						
1	HVAC Rough In	American Indoor	VAV delivery 2/25 - AHU 3/22 - Chiller 3/15							x	x	x	x	x	x							
1	Security Requirments for Building	Dan Motl	Install security							x	x	x	x	x								
1	Electrical	Electri-Tec	Pull wire							x	x	x	x	x								
1	Sprinkler	Hooper	Relocating heads and mains							x	x	x	x	x								
1	Studs and Drywall	Joe	Hang drywall/insulate wall							x	x	x	x	x								
1	3rd Floor Build out	Joe	Studs and drywall							x	x	x	x	x								
1	Tape and Prime	Livesey								x	x	x	x	x								
2	Ceilings	Central	Install ceiling grid							x												
2	Plumbing	Hooper	Install fixtures							x	x											
3	Doors	Joe	Install							x												
ISSUES																						

Last Planner Example CSHP PPC Calculation

BOLDT		Charter Street Heating Plant Rebuild		February 14, 2011		
Planned Percent Complete			82%			
Assignment Description			PPC Analysis			
REPEAT	Remember the Five Criteria for Release of Assignments Specific, Sound, Sequenced, Sized, Safe	Responsible Party	Activity Detail	Y	N	Reasons For Variance
	Technical Leadership Team					
	Monthly Master Schedule update	Gus	Issue wrap up to state	Y		
	Pencil review pay application	Jeff N.	review December invoice	Y		
General Project						
	steam vault	A&O	Design	N		Engineering/Arch
	Equipment Layout	Dan R.	I.06 to the W waiting on reconfiguration	Y		
	Waterproofing	G & C	P line going west to L.1 - 10.8 going N to 15 line - moving north along M Line	Y		
	Precast	Jeremy	Precast submittals	Y		
	Curtain wall	Jeremy	Issue contract and start shop drawings	N		Contract/C.O.s
	Metal Panels	Jeremy	Issue contract and start shop drawings	N		Contract/C.O.s
	Roofing	Jeremy	Review Proposals	N		Over projected
	Install Drain tile and backfill foundations	Joe	Underslab drainage - start at P line going west to L.1 - 10.8 going N to 15 line	Y		
	FRPS Building Foundation Walls	Joe	Pour walls - 16 line M to I.6	Y		
	FRPS Southeast Stair Tower 1st thru 5th - Stair #1	Joe	Place wall to 115'10"	Y		
	FRPS Interior Footings	Joe	form footings 15 Line to 11.1 - L to I.2	Y		
	Install Drain tile and backfill foundations	Terra	Back Fill - Start at 12.7 and P	Y		
	Mass Excavation	Terra	form footings 15 Line to 11.1 - L to I.2	Y		
Dayton Building						
GENERAL						
Superstructure						
	Review & approve 1st tier steel shop drawings	Andy		Y		
	Steel Material Shop Drawings	Skyline	Operating floor I.06 to the East	Y		
Boldt Construction Office						
	HVAC Rough In	American Indoor	VAV delivery 2/25	Y		
	Security Requirements for Building	Dan Moti	Install security	Y		
	Electrical	Electri-Tec	Continue rough in	Y		
	Sprinkler	Hooper	Rough In	Y		
	Studs and Drywall	Joe	Hang drywall/insulate wall	Y		
	3rd Floor Build out	Joe	Start door frames and studs	Y		
	Tape and Prime	Livesey		Y		


Last Planner Example CSHP PPC Trend Chart

Planned Percent Complete
CHARTER STREET HEATING PLANT REBUILD



Last Planner Example CSHP Plan Failure Chart

Variance Tracking Chart
CHARTER STREET HEATING PLANT REBUILD



BOLDT

Last Planner Coaching

Last Planner Score Card

Project Name _____ Project # _____

Legend: ○ - Not used ● - Needs improvement ● - Used well

Score	Item	Comments
	PPC (5 min)	
<input type="radio"/>	PPC is measured	
<input type="radio"/>	Plan failures are probed	
<input type="radio"/>	Review PPC trend	
	Lookahead Plan (15 min)	
<input type="radio"/>	A lookahead plan is utilized	
<input type="radio"/>	The team is prepared	
<input type="radio"/>	Dialogue on conflict occurs	
<input type="radio"/>	Activity screening is utilized	
	Constraint Analysis (included above)	
<input type="radio"/>	Constraints analysis is conducted	
<input type="radio"/>	Constraints are clearly defined	
<input type="radio"/>	Responsibility for constraint removal is clear	
	Commitment Plan/WWP (35 to 40 min)	
<input type="radio"/>	A commitment plan is developed	
<input type="radio"/>	Commitments are specific and clear	
<input type="radio"/>	Responsibilities and due dates are understood and freely agreed to	
<input type="radio"/>	Workable backlog is identified	
	Meeting Efficiency	
<input type="radio"/>	Meeting was a reasonable length	
<input type="radio"/>	Ground rules were utilized	
<input type="radio"/>	Formal feedback was sought	

Recommendations

Distribution

Project Mgr Facilitator Superintendent
 Group Mgr VP Gen Mgr VP Production Paul Reiser
 Regional Resource Specialist

Last Planner Meeting

Purpose

- Plan and control reliable production of work

Steps or Process

- Measure progress and learn how to plan better
- Shape work flow by understanding interdependencies
- Identify constraints
- Generate commitment for next week's work plan

Ground Rules

- Be on time for the meeting
- Be prepared
 - Will you finish last week's commitments.
 - What work is coming within the next six weeks.
 - What are your constraints?
- Plan to understand interdependencies and identify constraints. Do not plan to resolve constraints.
- Make commitments, do not use "I hope..."
- If you can't do it say so! (and tell us why)
- Turn off cellular phones
- Practice common courtesy
- Use "parking lot" or "issues board" for topics not requiring everyone's involvement.
- Evaluate the meetings once per month (+/Δ)

Outside the Last Planner Meeting

Score	Item	Comments
<input type="radio"/>	Master Schedule is updated regularly	
<input type="radio"/>	Master Schedule is divided into logical phases	
<input type="radio"/>	Phase schedules are developed and updated by the appropriate team (subs, designers, etc.)	
<input type="radio"/>	PPC trends are analyzed and appropriate action is taken	
<input type="radio"/>	Plan failures are summarized, root cause analysis is conducted and action is taken	

Recommendations

Last Planner Coaching

Last Planner Meeting

Purpose

- Plan and control reliable production of work

Steps or Process

- Measure progress and learn how to plan better
- Shape work flow by understanding interdependencies
- Identify constraints
- Generate commitment for next week's work plan

Ground Rules

- Be on time for the meeting
- Be prepared
 - Will you finish last week's commitments.
 - What work is coming within the next six weeks.
 - What are your constraints?
- Plan to understand interdependencies and identify constraints. Do not plan to resolve constraints.
- Make commitments, do not use "I hope..."
- If you can't do it say so! (and tell us why)
- Turn off cellular phones
- Practice common courtesy
- Use "parking lot" or "issues board" for topics not requiring everyone's involvement.
- Evaluate the meetings once per month (+/Δ)

Last Planner Coaching

<u>Score</u>	<u>Item</u>	<u>Comments</u>
<input type="radio"/>	<i>PPC (5 min)</i>	
<input type="radio"/>	PPC is measured	
<input type="radio"/>	Plan failures are probed	
<input type="radio"/>	Review PPC trend	
<input type="radio"/>	<i>Lookahead Plan (15 min)</i>	
<input type="radio"/>	A lookahead plan is utilized	
<input type="radio"/>	The team is prepared	
<input type="radio"/>	Dialogue on conflict occurs	
<input type="radio"/>	Activity screening is utilized	
<input type="radio"/>	<i>Constraint Analysis (included above)</i>	
<input type="radio"/>	Constraints analysis is conducted	
<input type="radio"/>	Constraints are clearly defined	
<input type="radio"/>	Responsibility for constraint removal is clear	
<input type="radio"/>	<i>Commitment Plan/WWP (35 to 40 min)</i>	
<input type="radio"/>	A commitment plan is developed	
<input type="radio"/>	Commitments are specific and clear	
<input type="radio"/>	Responsibilities and due dates are understood and freely agreed to	
<input type="radio"/>	Workable backlog is identified	
<input type="radio"/>	<i>Meeting Efficiency</i>	
<input type="radio"/>	Meeting was a reasonable length	
<input type="radio"/>	Ground rules were utilized	
<input type="radio"/>	Formal feedback was sought	

Last Planner Coaching

Outside the Last Planner Meeting

<u>Score</u>	<u>Item</u>	<u>Comments</u>
<input type="radio"/>	Master Schedule is updated regularly	
<input type="radio"/>	Master Schedule is divided into logical phases	
<input type="radio"/>	Phase schedules are developed and updated by the appropriate team (subs, designers, etc.)	
<input type="radio"/>	PPC trends are analyzed and appropriate action is taken	
<input type="radio"/>	Plan failures are summarized, root cause analysis is conducted and action is taken	

Recommendations

The Last Planner process

Facilitating the right conversations
with the right people
at the right time

Questions?

Jeff Niesen


Jeff.Niesen@Boldt.com

608-250-8414

BOLDT[®]

LAST PLANNER

Monroe Clinic Northwest Addition
Experience



Introduction

- Jeff Kenley – Senior Project Manager, CGS Monroe Clinic Northwest Addition
- Kyle Mainwaring – Assistant Project Manager Self-Perform Group and HVAC Manager
- Tony Buss – Assistant Project Manager Subcontractor Management and LEAN Leader



The Experience


- The Project
- How We Started
- Last Planner Start-up
- Implementation into Concrete
- Interior Pull Schedule
- Coordinating the Utility Connections
- Last Planner Documents



The Project




- Issued in Five Bid Packages
- Four Story – 235,000 SF
- New Emergency Department, Imaging, Operating Rooms, Pre/Post Op Rooms, Patient Rooms, ICU and Women's Center
- Parking and Exterior Improvements



The Project



- Server and Dining Space
- New Main Entrance and Four Story Connector



How We Started


- Bid Packages #1 - #4
- Bid Schedule
- Subcontractor Input Schedule
- Subcontractors to Meet the Schedule
- "Push" Schedule



Last Planner Start-Up




- Bid and Awarded Bid Package #5
- Implemented LEAN and “Pull” Scheduling
- LEAN Project Consulting Presentation & Training
- 1st Pull Session – Structure & Exterior



Implementation into Concrete

- Building Challenges
- MEP Contract Awards
- Typical Push Schedule
- Pull Schedule for SOG
- Sequence Adjustment



Scheduling Elevated Decks

- 3-D Coordination
- Elevated Deck Pull Sessions
- Wood knockers



Interiors Pull Schedule

Four Levels


- **Lower Level**
 - Imaging, Pharmacy, ED, Cardio
- **Lobby Level**
 - Prep & Recovery, OR's, PT
- **1st Floor**
 - Patient Rooms, ICU
- **2nd Floor**
 - Patient Rooms, LDRP, Kitchen, Chapel




Traditional Schedule

- Generalized
- Pre-Bid
- Estimated Sequence
- Estimated Durations

Pre-Construction Schedule - Lower Level





Division of Work Areas





Pull Session

- Project Team Input
- Precise Durations
- Detailed Sequence
- Proactive Approach




Lower Level Area B - Pull Session





Coordinating the Utility Connections

- MEP Site Utility Yard
 - Multiple Trade Coordination
 - Start – Finish Schedule
 - Subcontractor Requested




Coordinating the Utility Connections




Weekly Work Plan

WEEKLY WORK PLAN														
GROUP		C G SCHMIDT - KAHLER SLATER			CATEGORIES OF VARIANCE						TOTAL ACTIVITIES			
PROGRAM		MONROE CLINIC			1	Contracts/CO's	8	Qualified Staff Availabl	ACTIVITIES COMPLETED			42		
PROJECT		NORTHWEST ADDITION			2	Client Change	9	Materials/supplies avail	PERCENT PLANNED			32		
PROJECT NUMBER		080188			3	Submittals	10	Equipment	COMPLETE			76%		
RESPONSIBLE INDIVIDUAL		ROD MARRON			4	Arch/Eng/Design/RFI	11	Weather						
REPEAT	ASSIGNMENT DESCRIPTION	RESPONSIBLE PARTY	COMMENTS	5	Schedule/Coordination	12	Site Conditions							
				6	Prior Work Complete - Other	13	Incorrect Time Estimat							
				7	Prior Work Complete - Self	14	Off Project Demands							
				STARTING ON				10-Jan-11		PPC ANALYSIS				
				Mon	Tue	Wed	Thu	Fri	Sat	DONE?		Category		
				10-Jan	11-Jan	12-Jan	13-Jan	14-Jan	15-Jan	YES	NO		REASONS FOR VARIANCE	
	LOBBY LEVEL SOFFIT SOUTH	AUSTAD		X							X			HALLMARK / NATIONS
	2ND FLOOR CONNECTOR SOFFIT SOUTH	AUSTAD		X	X	X	X	X			X			6
	FRAME CLINIC CONNECTOR	CGS		X	X	X	X	X		X				
	DOOR FRAMES LOWER LEVEL - AREA C	CGS		X	X	X				X				
	WALL BLOCKING - LOBBY LEVEL AND LOWER LEVEL	CGS		X	X	X	X			X				
	BREAK DOWN GENERATOR ENCLOSURE WALL FORMS	CGS		X	X					X				
	PANELS AND CONDUIT IN CUP	FAITH		X	X	X	X	X		X				
	IN WALL ROUGH IN LOWER LEVEL (ALL AREAS WHERE AVAILABLE)	FAITH		X	X	X	X	X			X		DESIGN CHANGE PENDING	4
	OVERHEAD ROUGH IN ON 2ND FLOOR	FAITH		X	X	X	X	X		X				
	MISC CONDUIT ON LOBBY LEVEL	FAITH		X	X	X	X	X		X				
	LOWER LEVEL - SOFFITS AND BULKHEADS	HMARK		X	X	X	X	X		X				
	Z-FURRING & PLYWOOD - NORTH CONNECTOR	HMARK		X	X	X	X				X		JPC	6
	INSTALLING WATER MAIN ON 1ST FLOOR AREA B	HOOPER		X	X	X	X	X		X				
	TESTING MED GAS ON LOBBY LEVEL	HOOPER		X	X	X				X				
	INSTALLING MED GAS IN WALL LOWER LEVEL IN AREA C	HOOPER		X	X	X	X	X		X				
	INSTALLING PITCH PIPE AND HANGERS IN CUP	HOOPER		X	X	X	X	X		X				
	START MED GAS IN WALL AREA A - LOBBY LEVEL	HOOPER		X	X	X	X	X			X		OWNER	4
	HANGERS ON 1ST FLOOR AREA B BEHIND DUCT INSULATION	HOOPER		X	X	X	X	X		X				
	INSULATION ON LOWER LEVEL MAINS	HOOPER		X	X	X	X	X		X				
	IN WALL AREA B LOBBY LEVEL ON WATER AND WASTE	HOOPER		X	X	X	X	X		X				
	CONNECTOR GLASS	KD		X	X	X				X				
	INSTALL SUNSCREENS	KD		X	X	X	X	X		X				
	LB - INSTALL VAV BOX CONTROLLERS - WESTPHAL	MASTER		X	X	X	X	X		X				
	LB - MISC STAT ROUGH IN - WESTPHAL	MASTER		X	X	X	X	X		X				
	RA/SA DUCT MAINS 1ST - C AREA	NAMI		X	X	X				X				
	INSTALL F/S DAMPERS PENTHOUSE	NAMI		X	X					X				
	AHU-1 OVERHEAD DUCT ROUGH PENTHOUSE	NAMI		X	X	X	X			X				
	CORING HOLES FOR PIPING IN BLOCK WALLS CUP	NAMI		X	X						X			13




Variance Chart



WWP - Percent Complete

Planned Percent Complete



Constraint Log




MASTER CONSTRAINT LOG								
GROUP		C G SCHMIDT - KAHLER SLATER						
PROGRAM		MONROE CLINIC						
PROJECT		NORTHWEST ADDITION						
PROJECT NUMBER		080188						
RESPONSIBLE INDIVIDUAL		ROD MARRON						
CONST #	CONSTRAINT DESCRIPTION	DATE IDENTIFIED	IDENTIFIED BY	NEEDED BY	6-WEEK LOOK-AHEAD ID #	RFI#	RESPONSIBLE PARTY	ACTUAL COMPLETED DATE
		99	NO SECURITY PLANS FOR CONSTRUCTION	7/28/10	FAITH	8/16/10	A18320	
144	DNR PERMIT APPROVAL - BOILER STACK HEIGHT	10/21/10	NAMI	11/30/10		299	A/E	
151	EWC-1 SELECTION BY OWNER	12/2/10	HOOPER	12/17/10	A18350	463	OWNER	
160	DECISION ON HEADWALL	12/22/10	HOOPER	1/10/11	A20690		A/E & OWNER	
161	EQUIPMENT LAYOUT ROOMS: L409, L408, L406, L407, L602 (CB #19)	12/22/10	HOOPER	1/10/11	A19130	519	A/E & OWNER	
163	FIRE DAMPER NUMBER SEQUENCING	12/8/10	NAMI	3/14/11			OWNER	
166	CB-17 APPROVAL TO PROCEED WITH CHANGES	1/3/11	NAMI	1/19/11			OWNER	
167	NO UPS PLANS	1/13/11	FAITH	1/20/11			OWNER	
169	OR APPROVAL	1/13/11	FAITH	1/20/11	A23600		OWNER	
172	GRC ROOM LAYOUT (CB #19)	2/3/11	FAITH	2/10/11			A/E & OWNER	
173	ANGIO ROOM GLASS DOOR DECISION	1/26/11	CGS	2/10/11		534	OWNER	
174	ADDED CHEMICAL TREATMENT TO CHUTE	1/26/11	HOOPER	3/1/11	A22610	562	OWNER	
175	STEEL RADIATION AT OR EXTERIOR WALL	2/9/11	NAMI	3/14/11	A22580	552	A/E	
176	FPR AT EXTERIOR WALL IN REHAB GYM - L103A&B	2/9/11	NAMI	3/14/11	A23360	551	A/E	



LAST PLANNER

Questions & Answers



Plus

length of presentations was excellent
focused in on smaller pieces of lean
discounted student faculty rate
case studies of projects
local people providing case studies
sharing of information
mix of participants (different professions)
great attendance
varied experiences, common process

Delta

make sure schedule is correct
make powerpoints available ahead of time
provide a list of attendees - use LinkedIn